

**BOQ FOR RENOVATION WORK FOR THE OFFICE OF DIRECTORATE OF FINANCE AT
MAIN BUILDING OF SMI UNIVERSITY KARACHI**

ITEM	Description of Works	Unit	Qty.	Rate	Amount
A.	<u>CIVIL WORKS</u>				
1	Providing and fixing of 6'-6" high Aluminium glass partition for office cubicles with 5mm thick frosted glass, 4"-thick aluminium frame deluxe model (Lucky or Approved Equivalent), complete in all respect as per drawings and direction of the Engineer in charge.	sft	290		
2	Fixing of Aluminium glass door size 3'-0"x6'-6" for office cubicles having 4"-thick aluminium frame deluxe model (Lucky or Approved Equivalent), including 5mm thick hinges, handles etc. complete as per drawings and direction of the Engineer in charge.	Nos	1		
3	Removal of existing office cubicle made of 2" thick MDF with 1/4" paneeling on both sides including door and other hardware.	Sft	528		
4	Closing of existing doors of office, size 4'x9'-6" by providing and fixing ½" thick MDF ply including perral wood framing including screws/nails distempering paint matching with walls etc complete as per direction of Engineer.	Nos	2		
5	Removal of enamel paint (front side only) of existing office doors by scrapping and applying paint remover detergent including hardware, tower bolts, handles & door closers, etc complete as per direction of Engineer	Nos	2		
6	Removal of enamel paint (Both sides) of existing office doors by scrapping and applying paint remover detergent including hardware, tower bolts, handles & door closers, etc complete as per direction of Engineer	Nos	4		
7	Providing & fixing 5mmk thick colored glass in existing doors of office.	Sft	84		
8	Providing and applying two coats of distemper paint (Berger/ICI/Nelson or equivalent approved) on existing walls of faculty room including removal, scrapping of existing paint. Complete in all respect and as per directions of Engineer in Charge.	Sft	900		
9	Renovation, repairing & relocation of full height storage cabinet complete as per site and satisfaction of engineer incharge	Sft	90		
	Civil Work Sub Total				

**BOQ FOR RENOVATION WORK FOR THE OFFICE OF DIRECTORATE OF FINANCE AT
MAIN BUILDING OF SMI UNIVERSITY KARACHI**

TEM No	Description of Works	Unit	Quantity	Rate	Amount
B.	<u>ELECTRICAL WORKS</u>				
1	Multi Pin Plug A) Providing and fixing Multi pin plug Clipsal Australia or Equivalent, and wiring 2×7/0.029 plus 1×1.5sqmm S/C PVC Std insulated wire Pakistan cables or Equivalent, appropriate size of good quality PVC Pipe/Channel duct Adamjee or equivalent, surface/concealed in ceiling, wall and floors complete all respect, from Multi pin plug points to Distribution Board with all general Electrification works. As approved by engineer.	22	Nos.		
2	CEILING FAN 56" ; Providing and installation of Ceiling fan 56", 220V, With fan Dimmer switch Royal Deluxe fan or equivalent, copper winding, complete all respect including fixing work for ready to operate. As approved by Engineer.	2	Nos.		
3	SHIFTING OF SPLIT A.Cs UNITS ; Removing and re-fixing of Split A.Cs with copper pipe, proper joints and complete proper insulation, including drainage piping work. Check and fill gas if required, complete all respect for ready to operate.	1	Nos.		
Electrical Work Sub Total					

Grand Total Amount (A+B) : Rs. _____

Amount in Words: _____

Chairman Tender Committee